







MISCELLANEOUS PAPER HL-81-1

STABILITY OF RUBBLE-MOUND BREAKWATER MAALAEA HARBOR, MAUI, HAWAII

Hydraulic Model Investigation

Ьу


Robert D. Carver, Dennis G. Markle

Hydraulics Laboratory U. S. Army Engineer Waterways Experiment Station P. O. Box 631, Vicksburg, Miss. 39180

> January 1981 Final Report

Approved For Public Release; Distribution Unlimited





Prepared for U. S. Army Engineer Division, Pacific Ocean Fort Shafter, Hawaii 96858

CI

81 3 25 062

Destroy this report when no longer needed. Do not return it to the originator.

The findings in this report are not to be construed as an official Department of the Army position unless so designated by other authorized documents.

Unclassified WES/NF/+1-81 1

REPORT DOCUMENTATION PAGE	READ INSTRUCTIONS BEFORE COMPLETING FORM
	3. RECIPIENT'S CATALOG NUMBER
Miscellaneous Paper HL-81-1 AD-A096823	(4)
4. TITLE (and Subtitle)	S. TYPE OF REPORT & PERIOD COVERED
CONTRACTOR OF PURPLE MODELS PROPERTY.	(A . T.
STABILITY OF RUBBLE-MOUND BREAKWATER, MAALAEA HARBUR, MAUI, HAWAII, Hydraulic Model	Final report. Apr. Jun
HARBUR, MAUI, HAWAII, Hydraulic Model	6. PERFORMING ORG. NEPORT NUMBER
Investigation.	<u> </u>
7. AUTHORYO)	B. CONTRACT OR GRANT NUMBER(a)
Robert D. Carver	
Dennis G., Markle	
9. PERFORMING ORGANIZATION NAME AND ADDRESS	10 PROGRAM EL EMENT PROJECT TAGY
U. S. Army Engineer Waterways Experiment Station	10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
Hydraulics Laboratory	
P. O. Box 631, Vicksburg, Miss. 39180	
11. CONTROLLING OFFICE NAME AND ADDRESS	-12 MEDORT DATE
U. S. Army Engineer Division, South Pacific	Jan uary 19 81
Building 230	13. NUMBER OF PAGES
Fort Shafter, Hawaii 96858	50
14. MONITORING AGENCY NAME & ADDRESS(II dittorent from Controlling Office)	15. SECURITY CLASS. (of this report)
1	Unclassified
	Oliciassified
65	15. DECLASSIFICATION/DOWNGRADING
Approved for public release; distribution unlimite	d.
Approved for public release; distribution unlimite	
Approved for public release; distribution unlimite	
Approved for public release; distribution unlimite	
Approved for public release; distribution unlimite 17. DISTRIBUTION STATEMENT (of the abetract entered in Block 20, if different in	
Approved for public release; distribution unlimite 17. DISTRIBUTION STATEMENT (of the abetract entered in Block 20, if different in	
Approved for public release; distribution unlimite 17. DISTRIBUTION STATEMENT (of the abetract entered in Block 20, if different in	
Approved for public release; distribution unlimite 17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, 11 different in 18. SUPPLEMENTARY NOTES	om Report)
Approved for public release; distribution unlimite 17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, If different for 18. SUPPLEMENTARY NOTES	om Report)
Approved for public release; distribution unlimite 17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, 11 different for 18. SUPPLEMENTARY NOTES 19. KEY WORDS (Continue on reverse side 11 necessary and identity by block number Breakers (Water waves)	om Report)
Approved for public release; distribution unlimite 17. DISTRIBUTION STATEMENT (of the abstract entered in Black 20, 11 different for 18. SUPPLEMENTARY NOTES 19. KEY WORDS (Continue on reverse elds 11 necessary and identity by block number Breakers (Water waves) Breakwaters	om Report)
Approved for public release; distribution unlimite 17. DISTRIBUTION STATEMENT (of the obstract entered in Block 20, If different in 18. SUPPLEMENTARY NOTES 19. KEY WORDS (Continue on reverse side if necessary and identity by block number Breakers (Water waves) Breakwaters Hydraulic models	om Report)
Approved for public release; distribution unlimite 17. DISTRIBUTION STATEMENT (of the abstract entered in Black 20, 11 different for 18. SUPPLEMENTARY NOTES 19. KEY WORDS (Continue on reverse elds 11 necessary and identity by block number Breakers (Water waves) Breakwaters	om Report)
Approved for public release; distribution unlimite 17. DISTRIBUTION STATEMENT (of the abstract entered in Black 20, 11 different for 18. SUPPLEMENTARY NOTES 19. KEY WORDS (Continue on reverse elde 11 necessary and identity by block number Breakers (Water waves) Breakwaters Hydraulic models Maalaea Harbor, Hawaii Rubble-mound breakwaters	on Report)
Approved for public release; distribution unlimited 17. DISTRIBUTION STATEMENT (of the obstract entered in Block 20, 11 different in 18. SUPPLEMENTARY NOTES 19. KEY WORDS (Continue on reverse elds 11 necessary and identity by block number Breakers (Water waves) Breakwaters Hydraulic models Maalaea Harbor, Hawaii Rubble-mound breakwaters 20. ABSTRACT (Continue on reverse elds 11 necessary and identity by block number - An undistorted-scale hydraulic model study was	om Report)
Approved for public release; distribution unlimited 17. DISTRIBUTION STATEMENT (of the obstract entered in Block 20, 11 different in 18. SUPPLEMENTARY NOTES 19. KEY WORDS (Continue on reverse elds 11 necessary and identity by block number Breakers (Water waves) Breakwaters Hydraulic models Maalaea Harbor, Hawaii Rubble-mound breakwaters 20. ABSTRACT (Continue on reverse elds 11 necessary and identity by block number - An undistorted-scale hydraulic model study was adequacy of three breakwater cross sections consider	om Report) () () () () () () () () () () () () (
Approved for public release; distribution unlimited. 17. DISTRIBUTION STATEMENT (of the abetract entered in Black 20, 11 different in the supplementary notes. 18. SUPPLEMENTARY NOTES. 19. KEY WORDS (Continue on reverse side 11 necessary and identify by block number. Breakers (Water waves) Breakers (Water waves) Breakwaters Hydraulic models Maalaea Harbor, Hawaii Rubble-mound breakwaters 20. ABSTRACT (Continue on reverse side if necessary and identify by block number. - An undistorted-scale hydraulic model study was adequacy of three breakwater cross sections conside Maui, Hawaii. Plan 1 was protected by 6-ton doloss.	on Report) So conducted to investigate the cred for use at Maalaea Harbon se on both the sea side and
Approved for public release; distribution unlimited. 17. DISTRIBUTION STATEMENT (of the abetract entered in Block 20, 11 different in the supplementary notes. 18. SUPPLEMENTARY NOTES. 19. KEY WORDS (Continue on reverse elde 11 necessary and identify by block number. Breakers (Water waves) Breakwaters Hydraulic models Maalaea Harbor, Hawaii Rubble-mound breakwaters 18. ABSTRACT (Continue on reverse elde 11 necessary and identify by block number An undistorted-scale hydraulic model study was adequacy of three breakwater cross sections conside Maui, Hawaii. Plan 1 was protected by 6-ton doloss beach side, whereas Plans 2 and 3 used 6-ton doloss	conducted to investigate the cred for use at Maalaea Harbon se on both the sea side and se sea side and 7- to 10-ton
Approved for public release; distribution unlimited. 17. DISTRIBUTION STATEMENT (of the abetract entered in Block 20, 11 different in the supplementary notes. 18. SUPPLEMENTARY NOTES. 19. KEY WORDS (Continue on reverse side 11 necessary and identify by block number. Breakers (Water waves) Breakers (Water waves) Breakwaters Hydraulic models Maalaea Harbor, Hawaii Rubble-mound breakwaters 10. ABSTRACT (Continue on reverse side 11 necessary and identify by block number. - An undistorted-scale hydraulic model study was adequacy of three breakwater cross sections conside Maui, Hawaii. Plan 1 was protected by 6-ton doloss beach side, whereas Plans 2 and 3 used 6-ton doloss stone beach side. Plans 1 and 2 used 1V- on 2H-arr	conducted to investigate the cred for use at Maalaea Harbon se on both the sea side and se sea side and 7- to 10-ton nor slopes and Plan 3 used 1V-
Approved for public release; distribution unlimited 17. DISTRIBUTION STATEMENT (of the obstract entered in Block 20, 11 different in 18. SUPPLEMENTARY NOTES 19. KEY WORDS (Continue on reverse elds 11 necessary and identity by block number Breakers (Water waves) Breakwaters Hydraulic models Maalaea Harbor, Hawaii Rubble-mound breakwaters 20. ABSTRACT (Continue on reverse elds 11 necessary and identity by block number - An undistorted-scale hydraulic model study was adequacy of three breakwater cross sections consider	conducted to investigate the cred for use at Maalaea Harbon se on both the sea side and se sea side and 7- to 10-ton nor slopes and Plan 3 used 1V-

DD 144 72 1473 EDITION OF 1 NOV 88 IS GOSOLETE

Unclassified
SECURITY CLASSIFICATION OF THIS PAGE (Then Date Entered)

411389

1/11

SECURITY CLASSIFICATION OF THIS PAGE(When Date Entered)
20. ABSTRACT (Continued).
Plans 1, 2, and 3 are stable designs for the maximum breaking wave heights that can be expected to occur for 12- to 16-sec waves at swl's of -1 and +4 ft mllw. Also, Plans 2 and 3 can withstand attack of 16-sec, 15.2-ft breaking waves at an swl of +6 ft mllw and 16-sec, 16.7-ft breaking waves at an swl of +8 ft mllw without experiencing significant damage.

Preface

The model investigation reported herein was requested by the U. S. Army Engineer Division, Pacific Ocean (POD), in a letter to the U. S. Army Engineer Waterways Experiment Station (WES) dated 7 February 1980. The investigation was authorized by POD Intra-Army Order PODSP-CIV-80-21 dated 7 March 1980.

Model tests were conducted at WES during the period April through June 1980, under the general direction of Mr. H. B. Simmons, Chief of the Hydraulics Laboratory, and Dr. R. W. Whalin, Chief of the Wave Dynamics Division. Tests were conducted by Messrs. R. D. Carver and D. G. Markle, Research Hydraulic Engineers, and Mr. C. R. Herrington, Engineering Technician. Execution of this study and preparation of this report were performed by Messrs. Carver and Markle under the supervision of Mr. D. D. Davidson, Chief of the Wave Research Branch.

Liaison between POD and WES was maintained during the course of the investigation by telephone conversations and progress reports.

Commander and Director of WES during the conduct of the study and the preparation and publication of this report was COL Nelson P. Conover, CE. Technical Director was Mr. F. R. Brown.

Accession For	71
NTTS GRA&I	Z
U -mnounced Jiminication	
J	
Distr' tion	,
Avellehilit	
Dist Sp 1	
1	
1	

Contents

	Page
Preface	1
Conversion Factors, U. S. Customary to Metric (SI) Units of Measurement	3
Introduction	14
Purpose of Model Study	4
Design of Model	14
Test Equipment	6
Method of Constructing Test Sections	6
Description of Plans 1 and 2	7
Selection of Test Conditions	7
Test Results for Design Wave Conditions	8
Safety-Factor Tests of Plan 2	9
Rationale and Test Results for Plan 3	10
Conclusions	12
Photos 1-32	
Plates 1-6	

Conversion Factors, U. S. Customary to Metric (SI) <u>Units of Measurement</u>

U. S. customary units of measurement used in this report can be converted to metric (SI) units as follows:

Multiply	By	To Obtain	
feet	0.3048	metres	
miles (U. S. statute)	1.609344	kilometres	
pounds (mass)	0.4535924	kilograms	
pounds (mass) per cubic foot	16.01846	kilograms per cubic metre	
tons (2000 lb, mass)	907.1847	kilograms	

STABILITY OF RUBBLE-MOUND BREAKWATER MAALAEA HARBOR, MAUI, HAWAII

Hydraulic Model Investigation

Introduction

1. Maalaea Harbor is located on the west coast of Maui, one of the larger islands in the Hawaiian Island group (Plate 1). Pleasure boating, sport fishing, and commercial fishing have increased significantly during recent years and expansion of an existing small-boat harbor has been proposed. In order to provide wind wave and swell protection for the expanded harbor, it will be necessary to extend the existing south breakwater.

Purpose of Model Study

2. The original purpose of the model study was to experimentally investigate the adequacy of two breakwater sections proposed by the U. S. Army Engineer Division, Pacific Ocean (POD), for the south breakwater extension. Both sections used IV- on 2H-armor slopes. One alternative was protected by 6-ton* dolosse on both the sea side and beach side, whereas the other employed 6-ton dolosse sea side and 7- to 10-ton stone beach side. Later, following completion of tests for the two original plans, it was decided to also investigate a third plan using IV- on 1.5H-armor slopes in an attempt to reduce costs for construction of the breakwater.

Design of Model

3. Tests were conducted at an undistorted linear scale of 1:27.5, model to prototype. Scale selection was based on the size of

^{*} A table of factors for converting U. S. customary units of measurement to metric (SI) units is presented on page 3.

model armor units available relative to the estimated size of prototype armor units required for stability, the elimination of stability scale effects* and capabilities of the available wave tank. Based on Froude's model law** and the linear scale of 1:27.5, the following model-to-prototype relations were derived. Dimensions are in terms of length (L) and time (T).

Characteristics	Dimensions	Model:Prototype Scale Relations
Length	L	$L_{r} = 1:27.5$
Area	r_s	$A_{r} = L_{r}^{2} = 1:756$
Volume	L ³	$V_r = L_r^3 = 1:20,797$
Time	Т	$T_r = L_r^{1/2} = 1:5.24$

4. The specific weight of water used in the model was assumed to be 62.4 pcf and that of seawater is 64.0 pcf. Also, specific weights of model breakwater construction materials were not the same as their prototype counterparts. These variables were related using the following transference equation:

$$\frac{\left(\mathbf{W}_{\mathbf{r}}\right)_{\mathbf{m}}}{\left(\mathbf{W}_{\mathbf{r}}\right)_{\mathbf{p}}} = \frac{\left(\mathbf{\gamma}_{\mathbf{r}}\right)_{\mathbf{m}}}{\left(\mathbf{\gamma}_{\mathbf{r}}\right)_{\mathbf{p}}} \left(\frac{\mathbf{L}_{\mathbf{m}}}{\mathbf{L}_{\mathbf{p}}}\right)^{3} \left[\frac{\left(\mathbf{S}_{\mathbf{r}}\right)_{\mathbf{p}} - \mathbf{1}}{\left(\mathbf{S}_{\mathbf{r}}\right)_{\mathbf{p}} - \mathbf{1}}\right]^{3}$$

where

Subscripts m, p = model and prototype quantities, respectively $W_r = \text{weight of an individual armor unit or stone, lb}$ $\gamma_r = \text{specific weight of an individual armor unit or stone, pcf}$

^{*} R. Y. Hudson. 1975 (Jun). "Reliability of Rubble-Mound Breakwater Stability Models; Hydraulic Model Investigation," Miscellaneous Paper H-75-5, U. S. Army Engineer Waterways Experiment Station, CE, Vicksburg, Miss.

^{**} J. C. Stevens et al. 1942. "Hydraulic Models," Manuals on Engineering Practice No. 25, American Society of Civil Engineers, New York, N. Y.

 $L_{\rm m}/L_{\rm p}$ = linear scale of the model $S_{\rm r}$ = specific gravity of an individual armor unit or stone relative to the water in which the break-water is constructed, i.e., $S_{\rm r} = \gamma_{\rm r}/\gamma_{\rm w}$

 $\gamma_{..}$ = the specific weight of water, pcf

5. Crown protection for all plans will be provided by a cast-inplace concrete rib cage. It was assumed that the prototype rib cage
will be stable; therefore, it was not necessary that the model rib cage
be dynamically similar to the prototype. The model rib cage, constructed
of Plexiglas, was geometrically similar to the prototype, thus ensuring
proper reflection and dissipation of incident wave energy.

Test Equipment

6. Tests were conducted in a portion (100 ft long, 5 ft wide, and 3 ft deep) of an L-shaped concrete flume, which has overall dimensions of 250 ft long, 50 and 80 ft wide at the top and bottom of the L, respectively, and 4.5 ft deep. The flume layout is shown in Plate 2. A 44-ft (model) length of 1V-on-50H slope, representative of the existing prototype sea bottom, was molded and test sections were installed 29 ft beachward of the slope's toe. The test facility is equipped with a flap-type wave generator, capable of producing sinuscidal waves of various periods and heights. Test waves of the required characteristics were generated by varying the frequency and amplitude of the plunger motion. Changes in water-surface elevation as a function of time were measured by electrical wave-height gages in the vicinity of where the toe of the test sections was to be placed and recorded on chart paper by an electrically operated oscillograph. Measurement of wave heights (generator calibration) without test sections in place simulated existing conditions.

Method of Constructing Test Sections

7. Model breakwater sections were constructed to reproduce, as closely as possible, results of the usual methods of constructing

prototype structures. Core material, dampened as it was dumped by bucket or shovel into the flume, was compacted with hand trowels to simulate natural consolidation resulting from wave action during construction of the prototype breakwater. Once the core material was in place, it was sprayed with a low-velocity water hose to ensure adequate compaction of the material. Underlayer stone was then added by shovel and smoothed to grade by hand or with trowels but was not packed in place. Armor units used in the cover layer were placed in a random manner, i.e., laid down in such a way that no intentional interlocking of the units was obtained. Model elevations were controlled with an engineer's level to a tolerance of +0.005 ft.

Description of Plans 1 and 2

8. Plan 1, shown in Plate 3 and Photos 1-3, was constructed to a crown elevation of +13.0 ft mean lower low water (mllw) and used armor slopes of 1V on 2H both sea side and beach side. Crown protection was provided by a concrete rib cage, underlain with one layer of 6- to 8- ton stone. Individual concrete ribs were 15 ft long, 6 ft high, and 3 ft wide connected by two $3.0-\times1.5-\times1.5$ -ft concrete spacers which were flush with the top of the ribs at one-third points along the 15-ft length. The ribs used a 6-ft spacing center-to-center and in the prototype the bottom of each rib will be doweled to the stone underlayer. Both seaward and beachward slope protection was provided by 6-ton dolosse. Core stone weights of 100 to 500 lb were used, and the armor and core were interfaced with 1- to 2-ton underlayer stone. Plan 2 (Plate 4 and Photos 4-6) was the same as Plan 1 except that 7- to 10-ton stone was used to armor the beach side of the breakwater.

Selection of Test Conditions

9. Based on anticipated prototype wave conditions, it was decided that stability tests should consider 12-, 14-, and 16-sec wave periods at still-water levels (swl's) of -1.0 and +4.0 ft mllw. Model

observations indicated that for the selected wave periods and swl's, the corresponding maximum breaking wave was always more severe than any lesser wave height. Observations of incident wave forms at the structure showed that the worst breaking waves (as a function of wave period) which could be made experimentally to attack the section for the selected conditions were as follows:

swl ft mllw	Wave Period sec	Worst Freaking Wave Height ft
-1.0 -1.0	12.0 14.0	8.9 9.2
-1.0	16.0	10.5
+4.0	12.0	12.5
+4.0	14.0	12.6
+4.0	16.0	13.5

Model observations also indicated that due to consistently larger breaking wave heights, the 16-sec period condition was more severe than either the 12- or 14-sec period conditions. Wave heights at the 12- and 14-sec periods appeared to be very similar in severity. It was decided that for the range of wave conditions considered, the stability response of the test sections could be adequately evaluated by subjecting the test structures to the following storm surge hydrograph:

	swl	Test	Wave	Prototype	
<u>Step</u>	ft mllw	Period, sec	Height, ft	Duration, hr	Wave Type
	-1.0	14.0	4.6	0.33	Shakedown
1	-1.0	14.0	9.2	1.00	Worst breaking
2	- 1.0	16.0	10.5	1.00	Worst breaking
3	+4.0	14.0	12.6	1.00	Worst breaking
4	+4.0	16.0	13.5	1.00	Worst breaking
5	-1.0	14.0	9.2	1.00	Worst breaking
6	-1.0	16.0	10.5	1.00	Worst thraking

The above hydrograph is graphically depicted in Plate 5.

Test Results for Design Wave Conditions

10. During testing of Plan 1 some intermittent minor rocking of

- a few sea-side armor units was observed throughout the hydrograph and moderate wave overtopping during steps 3 and 4 caused minor rocking of a few beach-side armor units. Photos 7-9 show the test section after wave attack. A comparison of before- and after-test photographs shows that the final stabilized condition of the structure is virtually indistinguishable from its original appearance.
- 11. Plan 2 also exhibited an excellent stability response. Minor rocking of a few sea-side armor units was observed throughout the hydrograph; however, no displaced damage occurred. Even though moderate wave overtopping was present during steps 3 and 4, no damage was incurred by the 7- to 10-ton, beach-side armor stone. Photo 10 shows a 16-sec, 13.5-ft wave (step 4) impinging on the breakwater and Photo 11 shows the wave overtopping the structure. Photos 12-14 show the structure after completion of the hydrograph. Test results of Plans 1 and 2 were verified by a complete reconstruction and retesting.

Safety-Factor Tests of Plan 2

- 12. In designing rubble-mound breakwaters, or with any engineered structures, it is advantageous to determine what margin of safety is present in the selected designs. Consequently, at the conclusion of the repeat hydrograph test of Plan 2, it was decided to subject the structure to storm surges and wave heights in excess of the maximum design condition (16-sec, 13.5-ft waves at an swl of +4 ft mllw). A check of calibration data revealed that for the maximum design wave period of 16 sec, the wave generator was capable of producing depth-limited breaking waves for swl's up to +8 ft mllw. Therefore, even though POD realized swl's above the +4 ft mllw were extreme events, they requested Plan 2 be tested with 16-sec breaking waves at swl's of +6 and +8 ft mllw. Observations of incident wave forms at the structure showed that the worst breaking wave conditions which could be made experimentally to attack the section at the +6 and +8 ft swl's had heights of 15.2 and 16.7 ft, respectively.
 - 13. Following completion of the repeat hydrograph test of Plan 2,

the water level was raised to +6 ft mllw and the structure was subjected to 16-sec, 15.2-ft waves. This condition produced significant wave overtopping, resulting in displacement of two beach-side armor units. In-place rocking of 1 to 2 percent of the sea-side armor units (total number of dolosse used on the sea side of the model cross section was approximately 300 units) was observed; however, no displaced damage was experienced. Photos 15-17 show the after-testing condition of the breakwater.

- 14. Upon completion of testing at the +6 ft swl, the water level was raised to +8 ft mllw and the test section was subjected to attack of 16-sec, 16.7-ft waves. This condition produced major wave evertopping. Water coming across the structure did not directly strike exposed armor, and no further dislocation of beach-side armor was observed. Several sea-side armor units between +8 and +13 ft mllw shifted in their original positions, and 2 to 3 percent of the dolosse were observed to rock in place; however, no displaced damage resulted. Photos 18-20 show the final stability condition of the structure.
- 15. Plan 2 was subjected to wave attack for 2 hr (prototype) at each swl investigated. This duration of wave attack allowed sufficient time for the structure to stabilize, i.e., time for all movement of armor to abate.

Rationale and Test Results for Plan 3


16. Safety-factor tests of Plan 2 demonstrated that the structure was able to withstand attack of waves well in excess of the maximum design wave height; therefore, it was decided to investigate alternative schemes that might substantially reduce the structure's cost without sacrificing its functional performance. Some of the factors that govern material volume and, therefore, initial construction costs are elevation and width of the crown, type and weight of armor, and slope on which the armor is placed. Based on discussions between POD and the U. S. Army Engineer Waterways Experiment Station (WES), it was decided that in this particular study the greatest volumetric reductions with the least


probable impact on functionality could probably be achieved by steepening both seaward and beachward armor slopes from 1V on 2H to 1V on 1.5H. Based on this rationale, Plan 3 (Plate 6 and Photos 21-23) was identical with Plan 2 except for the steeper slopes.

- 17. Stability test results for Plan 3 were favorable. Minor rocking of a few sea-side armor units was observed throughout the hydrograph; however, no displaced damage occurred. Beach-side armor was undamaged, even though substantial wave overtopping was present during steps 3 and 4. It should be noted that as opposed to Plans 1 and 2, there appeared to be an increase in wave overtopping during attack of 14-sec, 12.6-ft waves (step 3) and 16-sec, 13.5-ft waves (step 4). Photos 24-26 show the breakwater after completion of the hydrograph. Reconstruction and retesting of the model section verified results of the initial test.
- 18. Plan 3 also was tested with 16-sec, 15.2-ft breaking waves at an swl of +6 ft mllw and 16-sec, 16.7-ft breaking waves at an swl of +8 ft mllw. Attack of the 16-sec, 15.2-ft breaking waves produced inplace rocking of 2 to 3 percent of the sea-side armor units; however, no displaced damage was observed. Beach-side armor was stable, even though major wave overtopping was experienced. Photos 27-29 show the after-testing condition of the structure. Wave attack at the +8 ft swl caused several sea-side armor units above the swl to shift in their original positions and 3 to 4 percent of the dolosse rocked in place; however, no displaced damage occurred. Also, beach-side armor stone was again stable. Photos 30-32 show the final stability condition of the structure.
- 19. As with Plan 2, Plan 3 was subjected to wave attack for 2 hr (pretetype) at each of the higher swl's (+6 ft mllw and +8 ft mllw). Again, this duration of wave attack allowed sufficient time for the structure to stabilize.
- 20. Stability test results of Plans 2 and 3 for the +6 and +8 ft swl's were very similar with slightly more in-place rocking of dolosse observed with Plan 3. Also, a moderate increase in wave overtopping and wave transmission was observed with Plan 3.

Conclusions

- 21. Based on the assumptions, tests, and results reported herein, it is concluded that:
 - a. Plans 1, 2, and 3 are stable designs for the maximum breaking wave heights that can be expected to occur for 12- to 16-sec waves at swl's of -1 and +4 ft mllw.
 - <u>b</u>. For safety-factor tests using extreme swl's, Plans 2 and 3 can withstand attack of 16-sec, 15.2-ft breaking waves at an swl of +6 ft mllw and 16-sec, 16.7-ft breaking waves at an swl of +8 ft mllw without experiencing significant damage.
 - Stability test results of Plans 2 and 3 are very similar with slightly more in-place rocking of dolosse observed at the +6 and +8 ft swl's for Plan 3.
 - As opposed to Plan 2, Plan 3 exhibited increased wave overtopping and wave transmission at the +4, +6, and +8 ft swl's.





人名 医乳球 克 医二氢化二氢二氢 医皮肤 医乳毒素 医乳毒素






Photo 3. Beach-cile view of Plan I before wave attack





Shaka a. Misa Viwa of Dan Pisathy ways attack






Beach-side view of Plan I before wave attack thoto 6.







13000 for Control to Most of Plan I affor completion of




| 現代の名称の 日本の本の (1987年) | 東京の 本代を 本代の大学ので






Shoto 11. Wide view of Stan 2 being overtoped by a News of the second




particle procession of the procession of atom-arms interested




the first property of the contract of the cont











CONTRACTOR SOLD FOR 15,040 Provider wared of the




Those in, Title view of Ham Paffer attack of Perce, I




ない オストリング こうけん ほんび をかいまでんしょ かいてんしん




Sequit-cite wiew of itam I after attuck of Pérce, IC.T-C President ware et an awit-cite wil of the President










しかけれる 多音な かんしょう ロター かしゅんじ コルコ・カステー プレスかいし






A STANDARD OF THE CONTRACTOR OF THE STANDARD O






THOSE OTHER STOME OF FRAME STANDARD SECTIONS OF THE SECTION OF SECTIONS OF THE SECTION OF THE SE



the south pully and the Photo 28. Goa-ribo view of the taffer attent



Hoto (%) Beath-of to view of Ham 3 after attack of N-rees, N and the Profile




Fig. 2. Cille view of Plan 3 after attack of 16-anc, 16.7-ft breaking waver at an axis 2. mlbs






Photo vi. Tea-sile view of ilan 3 after attack of 16-see, 16.7-ft breaking waves at an smit



Thoto 37. Seach-side view of Plan 3 after attack of 16-see, 16.7-ft Preaking waves at an swl of +9 ft willw







PLATE 2






PLATE 4




PLATE 5




PLATE 6

In accordance with letter from DAEN-RDC, DAEN-ASI dated 22 July 1977, Subject: Facsimile Catalog Cards for Laboratory Technical Publications, a facsimile catalog card in Library of Congress MARC format is reproduced below.

Carver, Robert D

Stability of rubble-mound breakwater Maalaca Harber,
Maui, Hawaii; hydraulic model investigation / by Motert B.
Carver, Dennis G. Markle. Vicksburg, Miss.: ". C.
Waterways Experiment Station; Springfield, Va.: available
from National Technical Information Service, 1981.
12, [32] p. [6] leaves of plates: ill.; 27 cm.
(Miscellaneous paper - U. S. Army Engineer Waterways
Experiment Station; HL-81-1)
Prepared for U. S. Army Engineer Division, Pacific
Ocean, Fort Shafter, Hawaii.

1. Breakers (Water waves). 2. Breakwaters. 3. Hydraulic models. 4. Maalaea Harbor, Hawaii. 5. Rubble-mound breakwaters. I. Markle, Dennis 7., joint author. II. United States. Army. Corps of Engineers. Pacific Ocean Division. III. Series: United States. Waterways Experiment Station, Vicksburg, Miss. Miscellaneous paper; HL-81-1. TA7.W34m no.HL-81-1.

DATE